# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24263

## APPROVED SCHEDULE - B

**No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017**

**Construction of new culverts in Coffee board layout, pampa extension, kempapura and surrounding areas in ward 07, Byatarayanapura**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of N VENKATA REDDY | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 318.4 | KSRB 2-2.2:Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ORDINARY soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches , stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and direction of the Engineer-in-charge. | Cum | 83.16 | Rupees Eighty Three and Sixteen Paise Only |
| 2 | 45.36 | KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . | Cum | 5070.6 | Rupees Five Thousand Seventy and Sixty Paise Only |
| 3 | 60.48 | KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. | Cum | 5490.72 | Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only |
| 4 | 90.72 | KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications. | Cum | 3456.0 | Rupees Three Thousand Four Hundred Fifty Six Only |
| 5 | 201.6 | KSRB 5.3-1:Providing ruled pointing of course stone msonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge. | Sqm | 35.64 | Rupees Thirty Five and Sixty Four Paise Only |
| 6 | 300.24 | Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification | Cum | 4484.0 | Rupees Four Thousand Four Hundred Eighty Four Only |
| 7 | 318.4 | KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification | Cum | 94.82 | Rupees Ninety Four and Eighty Two Paise Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

08/03